



Office of Public Safety

Tel: 902 368-4869
Fax: 902 368-5526

Department of Justice
and Public Safety

Provincial Fire Marshal

PO Box 2000
Charlottetown
Prince Edward Island
Canada C1A 7N8



January 22, 2026

To ensure the safety of patrons and vendors during the Cavendish Beach Music Festival and Sommo Festival, the Fire Marshal's Office has created the below checklist for vendors and activations to follow. Non-compliance with the items sited in the checklist will result in a suspension of that vendor's/activation's operations during the event.

Cavendish Beach Music Festival & Sommo Festival 2026 Vendor & Activation Checklist:

- Grill(s) and/or deep fryer(s) [any appliance creating grease laden vapours] shall be in a structure or trailer (no tents) with Fire Suppression and Ventilation installed in accordance with NFPA 96.
- Fire Suppression systems shall be certified and tagged within the last 12 months.
- All propane installations shall meet CSA B149.2-2020 Code and are subject to inspection by the Provincial Propane Inspector (Inspection Services). Tanks shall be installed on a solid base (ex. patio stone, wood, milk crate for smaller tanks) and be fastened securely to the trailer or structure (ex. ratchet straps, chains).
- Two additional fire extinguishers (min 10 lb ABC and Class K) shall be in all commercial cooking facilities that produce grease laden vapours and shall be certified and tagged within the last 12 months.
- All tents within the venue, regardless of use, shall meet NFPA 1 & 701, and shall be equipped with the necessary 10 lb ABC fire extinguisher(s) (certified and tagged within the last 12 months). *This includes awnings attached to vendors vehicles/trailers.*
- All spare propane tanks and flammable liquids shall be stored in the festival's central secure location protected from vehicle traffic and shall be marked with vendor's name.
- Propane BBQ's shall not be located under or near combustible materials or in tents.
- The use of individual generators for power shall only be permitted as a backup power source in the event of a power outage. During normal and back-up power operations, ensure no excessive use of extension cords and power bars.

A final pre-event site inspection will be completed on **08/Jul/2026 (CBMF) & 10/Sep/2026 (Sommo)** starting at **10:00am**. **ALL vendors/activations shall be setup and have staff present for inspections. A successful FMO inspection is required before you can begin operating.**